

SURVEY &
REMONUMENTATION

SEP 29 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

STATE OF MICHIGAN
OSCEOLA COUNTY
FILED

Osceola
(County)

Located in:

Corner Code: #

1. Public Land Survey

T 26N R 2E

D - 9

2. Property Controlling
in Section

S

S

S

S

3. Miscellaneous
Property in Sec.

S

S

S

S

4. Lot No. , Recorded Plat

5. Private Claims

Register of Deeds Stamp & File Number

14 SEP 94 11:08 A.M.

PATSY J. PETERS
REGISTER OF DEEDS

I, Marvin E. Myers, in a field survey on July 8, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO-July 1839 Coon

Mon-Post

WIT: 18" Y.Pine N71°W 11 lks.

3" Dwarf Oak S87°E 21 lks.

GLO-Oct. 1935 Guy Veal

Mon-3½" Brass Tablet in 6" Conc. Mon.

WIT: 6" J.Pine S50°W 64 lks.

9" B.Oak N61°W 96 lks.

July 1964 N.Caldwell

Mon-US GLO Mon.

No accessories noted.

L.1., pg.37 Dec. 1972 N.Caldwell

Mon-Fd, GLO Mon in Centerline E-W Road

WIT: RR Spike in top of GLO Stump N61°W 63.10'

Power Pole S70°W 96.30'

Large Fence Post N10°E 34.00'

Set 1" Pipe along Side Mon.

Power Pole S60°E 84.60'

L.2., pg.129 N.Caldwell

Same as L.1., pg. 37

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found GLO 6" Concrete Monument with 1" Pipe along East side of Monument and the GLO 6" Concrete Monument is accepted as a careful and faithful reestablishment of the position of the original corner.

APPROVED

County Remonumentation

Peer Review Group

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon-6" Concrete US GLO Monument with ¾" Dia. Brass Tablet

WIT: 1" Pipe along East side


Set 4" Pole Barn nail in SW side 7" Norway N30°W 38.42'

Fd. USFS Post N05°E 33.00'

Fd. Large Fence Post N17°E 34.00'

Face of Power Pole S54°E (recorded as S60°E) 84.60'

Face of Power Pole S81°W (recorded as S70°W) 96.30'



Signed by Marvin E. Myers

Date

Aug 23, 1994

Surveyor's Michigan License No. 31600