

# DEPARTMENT OF NATURAL RESOURCES STATE OF MICHIGAN

# **TIMBER SALE PROSPECTUS #6829**

SCHEDULED SALE DATE AND TIME: 3:00 p.m. (local time) on May 13, 2021. LOCATION: NAUBINWAY FIELD OFFICE, PO BOX 287, US 2 W11569, NAUBINWAY, MI 49762.

CONTACT NAME: Karen Rodock PHONE NUMBER: (906) 477-6048

PROSPECTUS NOTE: The bidder is advised to inspect the sale area and review the location, estimated volumes, operating costs and contract terms of proposed sales. Please be aware that some landowners may request 60 days or more notice for access across their land.

Notice is hereby given that bids will be received by the Unit Manager, SAULT STE MARIE MANAGEMENT UNIT, for certain timber on the following described lands:

Rich Logger Red Pine (45-103-20) / T43N, R06W, SEC. 25, S1/2NW,S1/2NE,NESE,S1/2SE.

T43N, R06W, SEC. 26, SENW, NE, NWSE.

T43N, R06W, SEC. 36, NWNW, SW, NWSE.

Mackinac County, Advertised Price \$339,718.50, 333.3 Acres, Red Pine.

SALE NOTE: A recreation site such as a trail, pathway, or campground is within the sale area or the vicinity. Certain restrictions/specifications may be applicable including time restrictions.

### TIMBER SALE INFORMATION

# Rich Logger Red Pine (45-103-20)

T43N, R06W, SEC. 25; T43N, R06W, SEC. 26; T43N, R06W, SEC. 36.

Mackinac County (Advertised Price \$339,718.50)

SALE NOTE: A recreation site such as a trail, pathway, or campground is within the sale area or the vicinity. Certain restrictions/specifications may be applicable including time restrictions.

A timber sale contract for this lump sum, sealed bid timber sale will be awarded to the responsible bidder offering the highest sealed bid price. All units of volume listed below were estimated using the T-Sale computer program and our traditional volume equations. Bids must be at or above the following advertised price for each product and species:

PRODUCTS & SPECIES **ESTIMATED UNITS\*** ADVERTISED PRICE Pulpwood 6.863 Cords 49.50 / Cord Red Pine

#### **BOND AND PAYMENT SCHEDULE:**

- 1. A bond in the amount of \$27,177.48 to insure faithful performance of the conditions of the contract will be deposited by the successful bidder within 21 days of the sale award.
- 2. Cutting in any sale or unit without the required advance payment would be considered a trespass.
- 3. Total payment must be paid in advance or according to the following schedule:
  - (a) Ten percent (10%) of the sale value must be paid within 21 days of the sale award.
  - (b) The 10% down payment will be credited towards the first unit cut.
  - (c) Payment for each of the following units must be made before cutting begins in that unit:

PAYMENT UNIT NUMBER	PERCENT OF TOTAL SALE VALUE
01	2.3%
02	4.1%
03	45.0%
04	7.5%
05	7.4%
06	20.1%
07	3.2%
08	10.4%

- 4. If no cutting takes place, the 10% down payment will not be refunded.
- 5. Operations on the contract issued will terminate on 06/30/2024.

# **SALE STATISTICS**

#### **SALE VOLUMES**

VOLUME			STATISTICAL RANGE IN CORDS		
TOTAL CUBIC FEET	TOTAL CORDS	PERCENT ERROR	MINIMUM	MAXIMUM	
542,184	6,863	11.74%	6,057	7,669	

<sup>\*</sup> The total volume is statistically estimated within plus (+) or minus (-) 11.74 percent. There are an estimated 6,863 cords on this timber sale, plus or minus 806 cords at the 95% confidence level. The estimated units are final and not subject to adjustment. Prospective bidders are urged to examine this timber and to make their own estimates of quantity and quality.

# **VDU VOLUMES**

A VDU is a Volume Determination Unit. Volumes and their associated statistics are calculated at the VDU level and summarized to the sale level. There is often a one to one relationship between a VDU and a Payment Unit, but not always, depending on the cruise design. Refer to the VDU TO PAYMENT UNIT table.

	VOLUME			RANGE IN CORDS	
VDU	TOTAL CUBIC FEET	TOTAL CORDS	PERCENT ERROR	MINIMUM	MAXIMUM
12	12,561	159	35.87%	102	216
27	22,270	282	19.03%	228	336
28	243,794	3,086	11.72%	2,724	3,448
29	40,701	515	15.19%	437	593
33	108,886	1,378	16.35%	1,153	1,604
37	56,572	716	15.20%	607	825
58	17,111	217	13.40%	188	246
62	40,282	510	18.08%	418	602
TOTAL:	542,177	6,863		5,857	7,869

### **VDU TO PAYMENT UNIT**

When a VDU is associated with more than one Payment Unit (PU), the VDU volumes are assigned to the PU based on acres of the VDU within the PU.

VDU	VDU ACRES	PU	PU ACRES
12	9.5	1	9.5
27	40.1	2	40.1
28	60.2	3	60.2
29	51.1	4	51.1
33	32.9	6	32.9
37	58.9	8	58.9
58	19.5	7	19.5
62	61.1	5	61.1
TOTAL:	333.3		333.3

# **DESCRIPTION OF TIMBER BY PU (PU)**

PU	MARKET GROUP	PRODUCT	QUANTITY	UNIT	ACRES	ADVERTISE PRICE
1	Red Pine	Pulpwood	159	Cords	9.5	\$7,870.50
2	Red Pine	Pulpwood	282	Cords	40.1	\$13,959.00
3	Red Pine	Pulpwood	3,086	Cords	60.2	\$152,757.00
4	Red Pine	Pulpwood	515	Cords	51.1	\$25,492.50
5	Red Pine	Pulpwood	510	Cords	61.1	\$25,245.00
6	Red Pine	Pulpwood	1,378	Cords	32.9	\$68,211.00
7	Red Pine	Pulpwood	217	Cords	19.5	\$10,741.50
8	Red Pine	Pulpwood	716	Cords	58.9	\$35,442.00
		TOTAL:	6,863	Cords		

# Sale Specific Conditions & Requirements

Sale Name: Rich Logger Red Pine Sale Number: 45-103-20 Seq#: 1

#### 1 - Sale Area

#### 1.2 - Boundaries

#### 1.2.1 - Painted boundaries (9/19)

The sale boundary and Payment Unit boundaries are marked and identified by blue, red, and yellow paint. Exterior sale boundary lines against forest service property are marked with blue paint. Exterior sale boundary lines against state are marked with red paint. Interior Payment Unit boundaries are marked with yellow paint. The painted boundary line trees are not Included Timber and are to be protected unless marked with orange paint. Yellow painted trees designating an interior Payment Unit boundary are only to be cut when all surrounding Payment Units have been paid.

### 2 - Timber Specifications

### 2.1 - Included Timber

# 2.1.1 - Clearcut unit(s) with unmerchantable trees (6/14)

Within Payment Unit(s) 3 & 6, cut all trees that are two (2) inches or more at DBH.

# 2.1.3 - Cut tree marked unit(s) (12/08)

Within Payment Unit(s) 1, 2, 4, 5, 7 & 8, all trees are designated for cutting when marked with orange paint above and below stump height, regardless of merchantability.

### 2.2 - Utilization

# 2.2.3 - Stump heights (4/07)

Stump heights within Payment Unit(s) 3 & 6 shall not exceed 6 inches for all trees. This is to facilitate planting operations.

#### 2.2.4 - Skidding length (2/14)

Skidding of lengths over 17 feet is permissible if the timber sale administrator approves the method and machinery used.

#### 3 - Payments

### 3.3 - Pre-measured Sales

# 3.3.4 - Dividing payment units (7/14)

Payment Unit(s) 2-6 & 8 may be divided at the request of the Purchaser and upon approval of the Unit Manager. Dividing Payment Units is a contract modification which requires a Timber Sale Contract Amendment. There will be only one division per Payment Unit, except Payment Unit 3 may be divided twice.

# 4 - Transportation

#### 4.1 - Construction

# 4.1.12 - No new roads (1/12)

No new roads will be permitted.

#### 4.2 - Maintenance

# 4.2.5 - Two wheel drive condition (2/04)

All existing trail roads on and adjacent to the sale area must be passable by two-wheel drive traffic for the duration of the sale.

#### 5 - Operations

# 5.2 - Conduct of Operations

#### 5.2.1 - Slash

# 5.2.1.12 - Slash for prescribed burning (1/05)

To facilitate prescribed burning, slash shall be moved at least 10 feet inside the sale boundary. Slash cannot be piled or placed near residual trees.

#### 5.2.2 - Hazard Trees/Snags

#### 5.2.2.1 - Den trees (10/16)

Obvious hollow and/or den trees shall be protected and left standing unless they are a safety hazard.

#### 5.2.4 - Dead and Down Creation

#### 5.2.4.3 - Dead and down creation, dead trees (6/07)

Except as provided for in General Condition and Requirement 5.2.2, no dead trees, standing or down, are to be cut, skidded, or processed.

# 5.2.38 - No decking against live trees (2/04)

Cut products may not be decked against unmarked or designated leave trees.

# 5.2.39 - ORV trail/route protection (4/18)

The Caffey Truck Trail & Carp River Truck Trail are ORV routes shown on the Timber Sale Map. Do not damage posts with yellow ORV markers. All stumps within 5 feet of the trail must be cut flush with the ground. Maintain a 20-foot-wide slash, debris, and rut free zone daily using the ORV trail or route as the centerline. Do not run equipment down the ORV trail or route. No decking of forest products will be permitted along the ORV routes. Skidding across the trail or route may only occur in locations approved by the sale administrator.

#### 5.2.41 - Snowmobile trail protection (9/11)

The Carp River Truck Trail and Caffey Truck Trail are snowmobile trails shown on the Timber Sale Map. Do not cut or damage posts with orange trail markers or traffic control signs. If the trail is used, it must be maintained and restored to a condition equal to or better than before the sale. The road maintenance/restoration must be done prior to December 1. If the trail is used for hauling, it must be graded to the satisfaction of the Unit Manager or his/her representative prior to December 1. If the trail road is to be used for hauling during the snowmobile season, then a snow-covered base must be left on the trail. At the point where the trail is no longer plowed, a berm cannot be allowed to build up. The transition back to the trail should be smooth and safe. Maintain a 20-foot-wide slash, debris, and rut free zone daily using the snowmobile trail as the centerline. No decking of forest products will be permitted along the snowmobile trail. All stumps within 5 feet of the snowmobile trail must be cut at ground level.

# 5.3 - Stream Protection

### 5.3.1 - Operating near stream (7/04)

No tracked or wheeled vehicles shall be operated within 50 feet of the Carp River. No crossings will be approved.

#### 5.4 - Soil Protection

#### 5.4.1 - Rutting restriction, general (7/16)

Operations are to cease immediately if equipment and weather conditions result in rutting of roads and/or skid trails which is 12 inches or greater in depth and 50 feet in length. The Unit Manager or his/her representative may restrict hauling and/or skidding if ruts exceed the specified depth. With the Unit Manager or his/her representative's approval, the Purchaser may return to the area when the risk of rutting has decreased.

# 5.8 - Protection of Endangered Species

# 5.8.5 - Protection of raptor nests (3/13)

All trees with raptor nests will be protected if found during harvesting operations. Notification will be made to the Unit Manager or his/her representative who will notify the Wildlife Biologist so an on-site evaluation and recommendation can be made, if necessary.

# 6 - Safety and Fire Prevention

#### 6.2 - Signing


#### 6.2.2 - Snowmobile trail posting (8/09)


The Purchaser is responsible for posting and maintaining caution signs on Carp River Truck Trail and Caffey Truck Trail prior to beginning operations during the snowmobile season (approximately December 1 to March 31). The trail must be posted 200 feet from the Sale Area to warn of logging activity and truck traffic. Signs must be removed when harvest operations are suspended or completed. The Purchaser will provide these signs.

# 6.2.3 - Recreational trail posting (2/10)

The Purchaser is responsible for posting and maintaining caution signs on Carp River Truck Trail and Caffey Truck Trail prior to beginning operations. The trail must be posted at appropriate distances from the Sale Area to warn of logging activity and truck traffic at both ends of the trail. Signs must be removed when harvest operations are suspended or completed. The Purchaser will provide these signs.

Section Name: Sale Specific Current as of 4/5/2021 10:49:05AM





# Rich Logger Red Pine Compartment 104 333.3 Acres





