

DEPARTMENT OF NATURAL RESOURCES STATE OF MICHIGAN TIMBER SALE PROSPECTUS #7432

SCHEDULED SALE DATE AND TIME: 9:00 a.m. (local time) on July 11, 2024. LOCATION: BARAGA MGMT UNIT, 427 US 41 NORTH, BARAGA, MI 49908.

<u>CONTACT NAME:</u> Brad Carlson <u>PHONE NUMBER:</u> (906) 353-6651

<u>PROSPECTUS NOTE:</u> The bidder is advised to inspect the sale area and review the location, estimated volumes, operating costs and contract terms of proposed sales. Please be aware that some landowners may request 60 days or more notice for access across their land.

Notice is hereby given that bids will be received by the Unit Manager, BARAGA MANAGEMENT UNIT, for certain timber on the following described lands:

Misery Mix (11-016-24) / T53N, R37W, SEC. 16, W1/2SW.

T53N, R37W, SEC. 17, NW,W1/2NE,E1/2SW,SE.

T53N, R37W, SEC. 18, NENE. T53N, R37W, SEC. 7, SESE. T53N, R37W, SEC. 8, SESW.

Ontonagon County, Advertised Price \$71,703.45, 202.9 Acres, Hardwood, Paper Birch.

SALE NOTE: Access may be through private land.

TIMBER SALE INFORMATION

Misery Mix (11-016-24)

T53N, R37W, SEC. 16; T53N, R37W, SEC. 17; T53N, R37W, SEC. 18; T53N, R37W, SEC. 7; T53N, R37W, SEC. 8.

Ontonagon County (Advertised Price \$71,703.45)

SALE NOTE: Access may be through private land.

A timber sale contract for this lump sum, sealed bid timber sale will be awarded to the responsible bidder offering the highest sealed bid price. All units of volume listed below were estimated using the Inventory Manager computer program and the new Michigan taper model. Bids must be at or above the following advertised price for each product and species:

ESTIMATE	D UNITS*	<u>ADV</u>	ERTISED PRICE
43.1	MBF	\$	63.00 / MBF
163.1	MBF	\$	113.00 / MBF
25.1	MBF	\$	195.00 / MBF
19.1	MBF	\$	109.00 / MBF
242	Cords	\$	4.35 / Cord
33	Cords	\$	15.30 / Cord
378	Cords	\$	19.20 / Cord
2,950	Cords	\$	10.65 / Cord
213	Cords	\$	10.15 / Cord
552	Cords	\$	2.15 / Cord
	43.1 163.1 25.1 19.1 242 33 378 2,950 213	163.1 MBF 25.1 MBF 19.1 MBF 242 Cords 33 Cords 378 Cords 2,950 Cords 213 Cords	43.1 MBF \$ 163.1 MBF \$ 25.1 MBF \$ 19.1 MBF \$ 242 Cords \$ 33 Cords \$ 378 Cords \$ 2,950 Cords \$ 213 Cords \$

^{*} The total volume is statistically estimated within plus (+) or minus (-) 23.63 percent. There are an estimated 4,956 cords on this timber sale, plus or minus 1,171 cords at the 95% confidence level. The estimated units are final and not subject to adjustment. Prospective bidders are urged to examine this timber and to make their own estimates of quantity and quality.

BOND AND PAYMENT SCHEDULE:

- 1. A bond in the amount of \$7,500.00 to insure faithful performance of the conditions of the contract will be deposited by the successful bidder within 21 days of the sale award.
- 2. Cutting in any sale or unit without the required advance payment would be considered a trespass.
- 3. Total payment must be paid in advance or according to the following schedule:
 - (a) Ten percent (10%) of the sale value must be paid within 21 days of the sale award.
 - (b) The 10% down payment will be credited towards the first unit cut.
 - (c) Payment for each of the following units must be made before cutting begins in that unit:

PAYMENT UNIT NUMBER	PERCENT OF TOTAL SALE VALUE
01	24.3%
02	19.8%
03	25.9%
04	17.1%
05	8.8%
06	4.1%

- 4. If no cutting takes place, the 10% down payment will not be refunded.
- 5. Operations on the contract issued will terminate on 06/30/2027.

SALE STATISTICS

Volumes were calculated in cubic feet using the Michigan taper model. Cubic foot volume includes all wood inside bark for the product indicated. For display purposes, cubic feet were converted to cords and MBF using a simple conversion factor, e.g. 79 cubic feet per cord and 185 cubic feet per MBF. The cubic foot volumes are precise; the cords and MBF volumes are not. Cubic foot volume cannot be directly converted to cords or boards with precision.

SALE VOLUMES

The total estimated sale volume may not equal the sum of the species/products due to the nature of statistical calculations associated with double sampling methodology.

VOLUME			STATISTICAL RANGE IN CORDS		
TOTAL CUBIC FEET	TOTAL CORDS	PERCENT ERROR	MINIMUM	MAXIMUM	
391,503	4,956	23.63%	3,784	6,127	

VDU VOLUMES

A VDU is a Volume Determination Unit. Volumes and their associated statistics are calculated at the VDU level and summarized to the sale level. There is often a one to one relationship between a VDU and a Payment Unit, but not always, depending on the cruise design. Refer to the VDU TO PAYMENT UNIT table.

	VOLUME			RANGE IN CORDS	
VDU	TOTAL CUBIC FEET	TOTAL CORDS	PERCENT ERROR	MINIMUM	MAXIMUM
14	172,344	2,182	18.45%	1,779	2,584
19	18,896	239	36.82%	151	327
21	174,127	2,204	17.35%	1,822	2,587
46	8,985	114	46.13%	61	166
60	17,152	217	33.10%	145	289
TOTAL:	391,503	4,956		3,958	5,953

VDU TO PAYMENT UNIT

When a VDU is associated with more than one Payment Unit (PU), the VDU volumes are assigned to the PU based on acres of the VDU within the PU.

VDU	VDU ACRES	PU	PU ACRES
14	78.2	1	43.1
		2	35.1
19	30.5	5	30.5
21	70.8	3	42.5
		4	28.3
46	17.5	5	17.5
60	5.9	6	5.9
TOTAL:	202.9		202.9

DESCRIPTION OF TIMBER BY PU (PU)

PU	MARKET GROUP	PRODUCT	QUANTITY	UNIT	ACRES	ADVERTISE PRICE
1	Paper Birch	Sawtimber	11.4	MBF	43.1	\$17,445.90
	Red Maple		46.2	MBF		
	Sugar Maple		6.2	MBF		
	Balsam Fir	Pulpwood	77	Cords		
	Mixed Aspen		115	Cords		
	Quaking Aspen		115	Cords		
	Mixed Hardwood		656	Cords		
	Red Maple		444	Cords		
	Sugar Maple		156	Cords		
	Yellow Birch		56	Cords		
	Mixed Spruce		41	Cords		
	White Spruce		41	Cords		
	Paper Birch		164	Cords		
2	Paper Birch	Sawtimber	9.2	MBF	35.1	\$14,222.55
	Red Maple		37.6	MBF		¥ : :,===::
	Sugar Maple		5.1	MBF		
	Balsam Fir	Pulpwood	63	Cords		
	Mixed Aspen		94	Cords		
	Quaking Aspen		94	Cords		
	Mixed Hardwood		535	Cords		
	Red Maple		362	Cords		
	Sugar Maple		127	Cords		
	Yellow Birch		46	Cords		
	Mixed Spruce		33	Cords		
	=		33	Cords		
	White Spruce					
	Paper Birch	0 1: 1	134	Cords	40.5	040,400,00
3	Paper Birch	Sawtimber	13.5	MBF	42.5	\$18,462.00
	Red Maple		46.1	MBF		
	Yellow Birch		7.6	MBF		
	Balsam Fir	Pulpwood	49	Cords		
	Mixed Aspen		92	Cords		
	Quaking Aspen		92	Cords		
	Mixed Hardwood		797	Cords		
	Red Maple		577	Cords		
	Sugar Maple		25	Cords		
	Yellow Birch		195	Cords		
	Mixed Spruce		77	Cords		
	White Spruce		77	Cords		
	Paper Birch		151	Cords		
4	Paper Birch	Sawtimber	9.0	MBF	28.3	\$12,290.20
	Red Maple		30.7	MBF		
	Yellow Birch		5.1	MBF		
	Balsam Fir	Pulpwood	32	Cords		
	Mixed Aspen		61	Cords		
	Quaking Aspen		61	Cords		
	Mixed Hardwood		531	Cords		
	Red Maple		385	Cords		
	Sugar Maple		16	Cords		
	Yellow Birch		130	Cords		
	Tellow Bilcii		l	Cords		
	Mixed Spruce		51	l Colus		
	Mixed Spruce		51 <i>51</i>	Cords		
	Mixed Spruce White Spruce			Cords		
5	Mixed Spruce White Spruce Paper Birch	Sawtimber	<i>51</i> 100	Cords Cords	48.0	\$6 313 7 <i>i</i>
5	Mixed Spruce White Spruce	Sawtimber	51	Cords	48.0	\$6,313.70

DESCRIPTION OF TIMBER BY PU (PU), CON'T

PU	MARKET GROUP	PRODUCT	QUANTITY	UNIT	ACRES	ADVERTISE PRICE
5 con't	Hemlock	Pulpwood	4	Cords		
	Mixed Aspen		16	Cords		
	Quaking Aspen		16	Cords		
	Mixed Hardwood		267	Cords		
	Ironwood		8	Cords		
	Red Maple		83	Cords		
	Sugar Maple		146	Cords		
	Yellow Birch		30	Cords		
	Mixed Spruce		3	Cords		
	White Spruce		3	Cords		
	Paper Birch		3	Cords		
6	Yellow Birch	Sawtimber	6.4	MBF	5.9	\$2,969.10
	Hemlock	Pulpwood	29	Cords		
	Mixed Hardwood		164	Cords		
	Red Maple		99	Cords		
	Sugar Maple		26	Cords		
	Yellow Birch		39	Cords		
	Mixed Spruce		8	Cords		
	White Spruce		8	Cords		
		TOTAL:	250.4	MBF		
		TOTAL:	4,368	Cords		

Sale Specific Conditions & Requirements

Sale Name: Misery Mix Sale Number: 11-016-24 Seq#: 1

1 - Sale Area

1.2 - Boundaries

1.2.1 - Painted boundaries (9/19)

The sale boundary and Payment Unit boundaries are marked and identified by blue and red paint. Exterior sale boundary lines against private property are marked with blue paint. Exterior sale boundary lines against state are marked with red paint. Interior Payment Unit boundaries are marked with red paint. The painted boundary line trees are not Included Timber and are to be protected unless marked with orange paint.

2 - Timber Specifications

2.1 - Included Timber

2.1.2 - Clearcut unit(s) w/o unmerchantable trees (8/11)

Within Payment Unit(s) 1-4 and 6, cut all trees which meet minimum piece specifications in 2.2 Utilization, except do not cut any mixed hardwoods that are twenty-two (22) inches or more at DBH, red oak, cedar, white pine or red pine. In addition, within Payment Unit 6, do not cut hemlock unless marked with red paint.

2.1.3 - Cut tree marked unit(s) (12/08)

Within Payment Unit(s) 5, all trees are designated for cutting when marked with orange paint above and below stump height, regardless of merchantability.

2.2 - Utilization

2.2.3 - Stump heights (4/07)

Stump heights within the Sale Area shall not exceed 12 inches for trees greater than 10 inches at DBH and 4 inches for trees smaller than 10 inches at DBH. A written waiver of this requirement may be obtained if wet summer weather makes winter logging necessary.

2.2.4 - Skidding length (2/14)

Skidding of unlimbed tops is not permissible. Skidding of lengths over 17 feet is permissible as long as the Sale Administrator approves the method and machinery used. If at any point damage exceeds specification 3.4.1, all of the remaining wood must be skid in lengths less than 17 feet.

2.2.7 - Uncut designated trees (2/04)

Liquidated damages of \$10.00 per tree will be assessed for every marked tree not cut.

2.2.8 - Utilization and removal (5/14)

All products meeting standards set forth in General Condition and Requirement 2.2 Utilization must be removed from the Sale Area. This is because excessive woody debris inhibits regeneration.

2.2.11 - Chipping restriction (9/14)

If chipping occurs on this sale, then no woody debris present on the ground at the start of the sale may be chipped. In addition, brush or chips may not be stored or stockpiled on-site for more than 30 days.

3 - Payments

3.4 - Damaged Timber

3.4.1 - Damaged timber (7/16)

General Condition and Requirement 3.4 Damaged Timber, defines liquidated damages for undesignated live merchantable trees which are cut or injured. In addition, extreme care should be taken to avoid damage to tree seedlings and saplings.

No damage is acceptable to undesignated live merchantable trees. Within the Sale Area, if more than 5% of trees (> 4.5" DBH) within a specified area of the sale are damaged, liquidated damages will be assessed for all trees damaged. Rates will

be in accordance with General Condition and Requirement 3.4 Damaged Timber.

4 - Transportation

4.1 - Construction

4.1.1 - Stream crossings, general (3/11)

All stream crossing structures will be temporary and therefore, shall be provided by the Purchaser, and must be removed upon completion of the sale. All permits for stream crossings will be provided by the DNR for crossings located on state land.

4.1.3 - Slash and earthen piles (8/04)

Piles or windrows of earth along roads and landings that have been widened or constructed shall be leveled. Slash from road maintenance or construction, including stumps, shall be dispersed throughout the sale, or be chipped, utilized or otherwise removed from the sale.

4.1.4 - Timber removed for construction (3/23)

Trees cut or damaged in the process of pre-approved road, landing or skid trail construction will be decked in an area separate from other Designated Timber and not removed until measured by the sale administrator. Payment will be made at contract prices or average prices, if not on the contract.

4.1.5 - Culverts (5/14)

Roads may require the installation of culverts for cross drainage or at natural drainage-ways. If culverts are needed in these locations, their placement will be specified by the Sale Administrator, and they shall be installed prior to hauling. The culverts shall be new, corrugated metal or plastic gauge. Culverts will be a minimum of 12 inches in diameter and 24 feet in length. If culverts are removed, fill shall be removed from wetland soils as specified. Soils shall be maintained and left in a non-erodible condition, with water bars, seed, fertilizer, mulch, and slash installed as directed by the Sale Administrator and as specified in the BMP manual. Stream crossing permits, if needed, will be obtained by the DNR for crossings located on state land.

4.1.6 - Road construction (1/09)

Construction of new roads or improvements of existing roads shall be done in such a way as to minimize the environmental and visual impacts. Merchantable trees shall be cut and utilized unless otherwise directed. Non-merchantable trees shall be severed and laid flat on the ground. Slash shall be scattered, and not left in windrows and kept a minimum of 10 feet back from the road edge, or be chipped, utilized or otherwise removed from the sale. Stumps shall be set upright, not left on edge, and be moved at least 10 feet away from the road edge. Disturbed soil shall be feathered into the woods and not left in berms or windrows.

4.1.7 - Road closure (10/11)

All new roads built into the sale must be blocked to vehicle traffic upon completion of the sale. Overgrown roads that are reopened shall be considered new roads. In general, this will require constructing a four (4') foot high berm of stumps and logs covered with earth. These roads must be rendered impassable to cars and trucks. Temporary berms may be required if no sale activity occurs for 30 or more consecutive days. Contact the Sale Administrator for specific details of design and placement.

4.2 - Maintenance

4.2.2 - Fill material (4/07)

To maintain roads, fill material may be needed in areas where "holes" exist or may be expected to develop. This fill material should be placed before trucking begins. Contact the Sale Administrator regarding the availability of onsite sand or gravel from adjacent State-owned lands.

4.2.4 - Grading (10/16)

For completion of the sale, state forest roads must be graded. In general, this will require a road grader or bulldozer to shape up the roads after forest products have been hauled off site. This includes cleaning of drainage areas, grading, crowning and filling with gravel, if necessary. The grading equipment to be used must be approved by the Unit Manager or his/her representative.

4.2.5 - Two wheel drive condition (2/04)

All existing trail roads on and adjacent to the sale area must be passable by two-wheel drive traffic for the duration of the sale.

4.4 - Access

4.4.1 - Private property access (3/11)

Permission for access across private land is the responsibility of the Purchaser. A copy of the written permission from the private landowner must be given to the Unit Manager within 30 days of the bid opening and prior to the beginning of operations.

5 - Operations

5.1 - Notification

5.1.1 - Pre-sale conference (10/16)

A pre-sale conference between the Purchaser and sale administrator is required prior to beginning any operations to determine landing and road locations. The Unit Manager or his/her representative must be contacted at least 10 days in advance to schedule the conference.

5.1.4 - Post-sale conference (10/16)

A post-sale conference on site between the Purchaser and sale administrator is required 5 days prior to the completion of active logging operations to determine clean-up and repair of landings, road edges, and the fulfillment of other contract specifications.

5.2 - Conduct of Operations

5.2.1 - Slash

5.2.1.1 - Slash within sale area (9/16)

No trees are to be felled outside the sale area and all slash is to be kept at least 10 feet back from the red & blue paint line. If sale boundary lines are along a public road or highway, then slash must be removed 50' from these lines per General Condition & Requirement 5.2.1.

5.2.2 - Hazard Trees/Snags

5.2.2.1 - Den trees (10/16)

Obvious hollow and/or den trees shall be protected and left standing unless they are a safety hazard.

5.2.3 - Operating Restrictions

5.2.3.2 - Operating restrictions (9/11)

Within Payment Unit(s) 1-6, all clean-up activities must be completed by June 30 of that year's harvest. This restriction is to allow clean-up areas to revegetate before the dry season.

5.2.3.3 - Bark slippage restriction (3/09)

Within Payment Unit(s) 5, unless changed by written agreement, cutting and skidding are not permitted during the period of April 15 to July 15. This restriction is because of bark slippage.

5.2.30 - Landing/road top soil protection (2/15)

Top soil on landings and new roads must be removed, stockpiled and saved. Upon completion of the timber sale, soil must be evenly distributed back over the area for revegetation. In addition, the area must be seeded and mulched per instructions of the Sale Administrator.

5.2.32 - Decking/landing restoration (9/13)

All decking and landing areas must have the surface area restored to a condition equal to or better than before. This is to ensure the proper regeneration of the stand. Wood debris, chips and "cookies" from trimmings must be removed or scattered away from landing and loading areas and may not be windrowed on the edge.

5.2.38 - No decking against live trees (2/04)

Cut products may not be decked against unmarked or designated leave trees.

5.4 - Soil Protection

5.4.1 - Rutting restriction, general (7/16)

Operations are to cease immediately if equipment and weather conditions result in rutting of roads and/or skid trails which is 12 inches or greater in depth and 50 feet in length. The Unit Manager or his/her representative may restrict hauling and/or skidding if ruts exceed the specified depth. With the Unit Manager or his/her representative's approval, the Purchaser may return to the area when the risk of rutting has decreased.

5.8 - Protection of Endangered Species

5.8.5 - Protection of raptor nests (3/13)

All trees with raptor nests will be protected if found during harvesting operations. Notification will be made to the Unit Manager or his/her representative who will notify the Wildlife Biologist so an on-site evaluation and recommendation can be made, if necessary.

Section Name: Sale Specific Current as of 5/24/2024 1:35:59PM



