



DELIVERED TO NEWAYGO CO.
02/09/2007 11:46:35 AM

SURVEY & REMONUMENTATION

2006 Newaygo County Remonumentation Project

FEB 28 2007

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Newaygo
(County)

SECTION

Located in: Corner Code #

1. Public Land Survey

T 14 N	R 11 W
T N	R W
T N	R W
T N	R W
T N	R W
T N	R W
T N	R W
T N	R W

VOL. 5 232

2. Property Controlling
in Section S
3. Miscellaneous S
Property in Sec. S



LINDA M. LANDHEER
NEWAYGO COUNTY REGISTER OF DEEDS
RECEIVED AND RECORDED
02/09/2007 11:47:49 AM

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

I, Norman L. Ochis, in a field survey on February 2, 2006 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 2, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 2 corners, all in the same town and range, may be Recorded on this certificate.

Section corner common to Sections 13, 14, 23 and 24, Goodwell Township.

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

GLO - J.H. Mullett
1st Quarter 1839
Set post corner
#1 10" Beech N36°E 10 links (6.6')
#2 18" Pine S42°W 15 links (9.9')

William M. Jacques (County Surveyor)
July 1, 1907 Book 23, Page 10
#3 30" Pine Stump N43°W 54 links (35.64')

Newaygo County Road Commission Sheet
1950± Axle Shaft and Stone
#4 15" Black Oak N35°E 67.1'
#5 6" Black Oak S40°E 32.1'

Robert L. Wetherell R.L.S. #24624
May 1966 Found Axle Shaft and Stone
#6 12" Black Oak S39°W 31.75'
#5 16" Black Oak S19°E 32.17'
#7 16" Black Oak S54°E 44.30'
#8 3" Black Oak N01°W 22.75'

B. DESCRIPTION OF CORNER EVIDENCE FOUND AND/OR METHOD APPLIED IN RESTORING OR REESTABLISHING CORNER:

I found a 1" x 30" axle in nest of 5" stones. The corner is in centerline of East and West gravel road. The condition of the witnesses are as follows: #1 thru #4 are gone, #5 thru #8 are in good condition.

C. DESCRIPTION OF MONUMENT FOR CORNER AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATING THE POSITION OF THE CORNER:

I removed the axle and set a 2 1/2" diameter Harrison cast iron monument 20" long marked "County Survey #22439" at ± .5' below grade as A substantial marker for the Section corner and is accepted as a careful and faithful reestablishment of the position of the original Section corner.

#6 14" Black Oak S32°W 31.80'
#5 20" Black Oak S24°E 32.15'
#7 20" Black Oak S59°E 44.28'
#8 6" Black Oak N06°W 22.82'

Found spike in East side
Found spike in West side
Found spike in NE side
Set 40d spike with tag in West side

Signed by Norman L. Ochis
Norman L. Ochis

Date February 5, 2007

Surveyor's Michigan License No. 22439

Form approved by Michigan State Board of Land Surveyors, Jan. 28, 1971
Revised May 14, 1975
Revised Jan., 1983

Approved by Peer Review Group on June 29, 2006
Norman L. Ochis, County Representative.

M.L.O.

